

# Butoni Wind Farm Project

(Fiji Electricity Authority)

## LEARNINGS

**Technical Visit & Workshop to Share Best Practices in Renewable Energy**

**Vila & Santo, Vanuatu**

**3-7 August 2009**

**Uate Biutanaseva**

Unit Leader Renewable Generation  
Fiji Electricity Authority





# Outline

- FEA
- Introduction
- Project Background
- Issues
- Learnings



## FEA's Mission and Vision

### VISION

"Energising our people and our nation"

### MISSION

"We will provide clean and affordable energy solutions to Fiji and the Pacific. We aim to provide all energy through renewable resources by 2011"




## Introduction

- FEA's first wind farm feeding into the national grid from Sigatoka region
- The Butoni Wind Farm Site is located in the south-western part of the Viti Levu Island of Fiji near Sigatoka township.
- The average elevation of the main ridge is about 220 mASL.
- The wind regime is dominated by south-easterly trade winds with small occurrences of sea breezes.



# Distribution Areas





## Project Background

- 2003
  - The FEA in line with its mission to produce all energy by renewable sources by the year 2011 decided to embark on a wind farm project.
  - FEA and Pacific Hydro Ltd (PHL) met with Department of Energy (DOE) and made site visits to all the sites where DOE had already taken wind measurements.



## Project Background

- 2004
  - Butoni, one of the sites close to where wind data was collected by DOE was chosen due to:
    - easy accessibility,
    - proximity of the Butoni ridge to the FEA grid
    - and Sigatoka being an area of increasing development,

SEL decided to install a wind monitoring tower on the Butoni ridge to get more accurate wind data.



## Project Background

- Initial data collected put Butoni in the low wind speed category with average wind speeds recorded at 4 - 6m/s. Project deemed financially uneconomical by PHL based on the development cost and the expected energy generation.
- FEA decides to pursue project on own accord as JV partner (PHL) pulls out of the project.
- PB Power (Australia) taken onboard by FEA as principal consultants to prepare documentation for tender.
- International tender called by FEA in Q4 2004





## Project Background

2005

- March 2005 – memorandum of understanding and confidentiality agreement signed between Vergnet and FEA
- July 2005 – design, supply and installation contract was signed between Vergnet Pacific and FEA for a 10MW Turnkey Wind Farm Project.
- Civil tender specification prepared by Vergnet. Civil scope included road works, platforms works, drilling and concrete works.



## Project Background

- Environmental Impact assessment concluded with final approval from Department of Environment
- Landowners sent on an excursion in New Caledonia in October to visualise what a wind farm looks like and the impact on their land.
- Full landowner and NLTB consensus to lease FEA land for the wind farm granted in November 2005
- Official start date of the contract was agreed to be **23 November, 2005** by both parties. Vergnet's 14 months period from ground works to commissioning commenced on the 23<sup>rd</sup>.



## Project Background

- 2006
  - Commissioning start April 2006 and last turbine commissioned in August 2007



## Wind Farm Data

The wind farm is made of:

- 37 wind turbines (GEV-MP 275)
  - Horizontal axis, 2 blades
  - Tower Height of 55m & Rotor Dia of 32m
  - Collapsible tower
- Each having a rated power output of 275KW
- Total rated capacity 10MW

The Performance Warranty under this Turnkey Contract is **11.3GWH** for a period of one year at an average wind speed of **5.47m/s**.



# Issues


- Landowners
  - Land approvals for the project were finally issued in November 2005.
- Surveying error
  - The initial errors by the Surveyors contributed to significant delays.
- Re submission of specifications
  - A lot of the works on the road lost momentum during the Christmas break due the re-drafting of the civil specifications. The contractor did not had clear instructions during this period on what specifications to follow.
- Drilling contractor
  - Lack of a competent drilling contractor has caused some delay on the overall project plan as well.



# Issues


- Weather
- Lack of proper design of roads and platforms
- Lack of understanding by Vergnet of local conditions and design tolerances.
- Full understanding of the Agreement/Contract when dealing with overseas companies.
- Having a proper O&M Agreement in place well before the actual operation starts.

# Performance



Monthly Wind Speed in Fiji, according to NASA


# Performance



**Power Curve for a Vergnet GEV-MP275 turbine (manufacturer's data)**



# Performance





## Performance

- Annual Average Wind speed recorded at the windfarm during the first year was  $\approx 4.96$  m/s
- Capacity Factor for first year of operation at 5.2% compared to 12% as manufacturer performance contract
- O&M Cost expected to increase after few years of operation – due to wear & tear and component life



## Learnings

- Land for any development must always be dealt in advance due to the process involved plus uncertainty with the landowners themselves
- Involvement of plant users during design stage of any development is absolutely vital.
- Proper understanding of the agreements or contracts for each project is a must to avoid issues, extra costs and delays.
- Proper storage of any project data and documents is very important – from investigation to operation



## Learnings

- Proper closing off projects – sign off for achievable design outputs
- Proper management of contractors or subcontractors is very important as mistakes or errors always lead to delay of project completion and increase in costs. Project management skills are a must for timely and smooth flow of project activities.
- Consider the maintenance cost carefully during selection stage of plant and equipment.















**THANK YOU**